

APPLETREE INTERIORS

FACTORY STANDARD OPERATING PROCEDURES

"Let Us Fulfill Your Dream Into Reality"

Document Title	Factory Standard Operating Procedures (SOP)
Organization	Appletree Interiors
Location	Calicut (Kozhikode), Kerala, India
Document Code	ATI-FSOP-2025
Version	1.0
Effective Date	18 June 2026
Approved By	Director — Yaseen
Review Cycle	Annually or upon process change

This document establishes the Standard Operating Procedures (SOP) for all factory operations at Appletree Interiors. It defines responsibilities, process steps, quality checkpoints, and accountability for every stage from material receiving to final dispatch. All factory staff are required to read, understand, and strictly follow these procedures.

■ *NOTE: No process may be executed without following the corresponding SOP. Any deviation must be reported to the respective Department Head immediately.*

ATI-FSOP-2025 | TABLE OF CONTENTS

No.	Section	Page
1	Company & Factory Overview	3
2	Staff Register & Responsibilities	4
3	SOP-01: Material Receiving & GRN	5
4	SOP-02: Store Management	7
5	SOP-03: Production – Modular Furniture	9
6	SOP-04: Production – Custom Wood Furniture	12
7	SOP-05: Quality Control (QC1/QC2/QC3)	15
8	SOP-06: Packing & Dispatch	18
9	SOP-07: Daily Factory Routine	20
10	Forms & Checklists Index	22

ATI-FSOP-2025 | SECTION 1 — COMPANY & FACTORY OVERVIEW

1.1 About Appletree Interiors

Appletree Interiors is a Kerala-based interior design and turnkey execution company with 22+ years of experience in the furniture and interior industry. The company operates its own manufacturing facility equipped with imported European machinery, skilled carpenters, dedicated designers, site engineers, and project management professionals.

Appletree Interiors delivers customized residential and commercial interiors that are aesthetically appealing, highly functional, durable, and budget-friendly, serving clients across Calicut, Kannur, Malappuram, Wayanad, Palakkad, and the wider Kerala region.

1.2 Factory Departments

Dept. Code	Department Name	Department Head	Scope of Work
MOD	Modular Furniture	Raees	Modular kitchens, wardrobes, TV units, work areas, storage systems
CWF	Custom Made Wooden Furniture	Shafeer	Beds, dining units, custom cabinets, wooden paneling, solid wood pieces

1.3 Factory Operating Hours

Day	Start Time	End Time	Attendance
Monday – Saturday	8:30 AM	6:00 PM	Mandatory
Sunday	—	—	Off (unless project emergency)

1.4 Core Factory Principles

- No material purchase without an approved Material Request (MR).
- No production without an approved Production Card.
- No dispatch without a QC Approval and Material Dispatch Note (MDN).
- No project closes without a completed Site QC (QC3) form.
- Every deviation from SOP must be reported to the Department Head on the same day.

ATI-FSOP-2025 | SECTION 2 — STAFF REGISTER & RESPONSIBILITIES

2.1 Factory Staff Register

No.	Name	Designation	Department / Area	Key Accountability
1	Yaseen	Director	Overall Operations	Final approver — Purchase & Billing. Strategic oversight.
2	Shafeer	Head of Wood Working	Custom Wooden Furniture (CWF)	All custom wood production quality, carpentry team, timelines.
3	Raees	Head of Modular Furniture	Modular Furniture (MOD)	All modular production quality, machine planning, assembly.
4	Afsal	Admin & Project Coordinator	Admin / Cross-functional	Production scheduling, project coordination, documentation.
5	Vibin	Store In-Charge	Purchase & Stores	Material receipt, GRN, stock monitoring, issue to production.
6	Hashim	Site Supervisor	Site / Installation	Site execution, installation quality, client coordination.
7	Noushad	Site Supervisor	Site / Installation	Site execution, installation quality, client coordination.
8	Sharat	BDE	Sales & Lead	Lead generation, client meetings, proposals, follow-ups.
9	Basith	Accounts Head	Accounts	Vendor payments, client billing, cost tracking, profitability.
10	Mohanan	Cleaning & Maintenance	Factory & Site	Factory cleanliness, equipment upkeep, site cleaning.

2.2 Accountability Matrix by Process

Process	Responsible Person	Approver	Escalation To
Lead & Sales	Sharat	Director (Yaseen)	Director
Design & BOQ	Designer	Design Head	Director
Material Request	Shafeer / Raees	Afsal (PM)	Director
Purchase Order	Vibin	Director (Yaseen)	Director
GRN & Store Entry	Vibin	Afsal	Director
Material Issue	Vibin	Afsal (PM)	Department Head
Modular Production	Raees	Afsal	Director
Wood Production	Shafeer	Afsal	Director
Factory QC (QC2)	Raees / Shafeer	Afsal	Director

Process	Responsible Person	Approver	Escalation To
Packing & Dispatch	Vibin + Dept Head	Afsal	Director
Site Installation	Hashim / Noushad	Afsal (PM)	Director
Site QC (QC3)	Hashim / Noushad	Afsal	Director
Client Billing	Basith	Director (Yaseen)	Director
Cleaning & Maint.	Mohanan	Dept Head on duty	Afsal

ATI-FSOP-2025 | SOP-01 — MATERIAL RECEIVING & GRN

Purpose

To ensure that all materials received at the factory are verified, inspected, documented, and stored correctly before being issued to production.

Scope

Applies to all incoming materials including plywood, HDHMR, PVC boards, laminates, veneers, hardware, paint, glass, and aluminium sections.

Responsible Staff

- Primary Responsible: Vibin (Store In-Charge)
- Inspection Support: Shafeer (CWF) / Raees (MOD) — depending on material type
- Documentation Approval: Afsal (Admin & Project Coordinator)

Step-by-Step Procedure

Step 1	Purchase Order Verification
Vibin verifies incoming delivery against the approved Purchase Order (PO). No material is accepted without a matching PO. If no PO exists, material is rejected and vendor is sent back. Afsal is informed immediately.	
Step 2	Physical Count & Inspection
Vibin counts all items in the presence of the delivery person. Shafeer or Raees inspects material quality: plywood thickness, laminate colour, hardware brand, glass type, moisture content of wood boards.	
Step 3	QC1 — Raw Material Check
Vibin and respective Dept Head verify: Thickness (plywood/HDHMR/PVC), Brand match with PO, Moisture level (wood boards), Colour and finish (laminates/veneers), Quantity count. Any rejection is recorded with reason and vendor is notified within 2 hours.	
Step 4	Goods Receipt Note (GRN) Creation
Vibin prepares GRN immediately after acceptance: GRN Number, Date, Vendor Name, PO Reference, Item-wise details (qty, unit, rate), Condition (Good / Partial / Rejected), Received by (Vibin signature), Verified by (Shafeer or Raees signature).	
Step 5	Store Entry & Bin Allocation
All accepted materials are labelled with a QR code sticker showing: Item Name, Thickness/Grade, Date Received, GRN Number. Materials are stored in their designated bin/rack area. Vibin updates the Stock Register immediately.	
Step 6	GRN Forwarding
GRN copy sent to: Afsal (for project records), Basith (for vendor payment processing), Director (for monthly review).	

■ NOTE: No material is to be taken from the store without a signed Material Issue Slip. Verbal requests are NOT accepted.

QC1 — Raw Material Incoming Checklist

No.	Check Point	Done	Remarks
1	PO number matches delivery challan	☐	
2	Supplier name matches PO	☐	
3	Quantity received matches PO quantity	☐	
4	Plywood / HDHMR thickness verified with calliper	☐	
5	Brand/grade matches specification	☐	
6	Moisture content checked (max 12% for wood boards)	☐	
7	Laminate colour/finish matches sample	☐	
8	Hardware brand verified (EBCO / Sleek as specified)	☐	
9	Glass type and thickness verified	☐	
10	No visible damage, warping, or delamination	☐	
11	QR code label affixed to all materials	☐	
12	GRN prepared and signed	☐	

Sign-Off

Role	Name	Signature	Date
Store In-Charge	Vibin		
Dept. Head (MOD/CWF)	Raees / Shafeer		
Admin & Project Coord.	Afsal		

ATI-FSOP-2025 | SOP-02 — STORE MANAGEMENT

Purpose

To maintain accurate, real-time stock records of all materials and ensure controlled, documented issuance of materials to the production floor.

Responsible Staff

- Primary: Vibin (Store In-Charge)
- Oversight: Afsal (Admin & Project Coordinator)
- Approval of Material Issue: Afsal (PM)

Stock Categories

Category	Items	Unit of Measure	Reorder Level
Boards	Marine Plywood (IS 710), HDHMR, PVC Board	Sheets	20 sheets
Laminates	All brands and finishes	Sheets	15 sheets
Veneers	Raw veneer, pre-finished	Sheets	10 sheets
Hardware	Hinges, channels, handles, soft-close units	Nos / Set	Project-wise
Paint	PU, melamine, wood primer	Litres	10 litres
Glass	Toughened, fluted	Sq. ft.	Project-wise
Aluminium	Sections, frames	Running ft	Project-wise

Stock Register Format

Vibin maintains a physical Stock Register and a digital copy (Excel/ERP) updated daily:

Item	Grade/Spec	Opening Qty	Received	Issued	Balance	Remarks
19mm Marine Ply	IS 710	100 sheets	50 sheets	90 sheets	60 sheets	—
12mm HDHMR	Grade A	80 sheets	30 sheets	60 sheets	50 sheets	—

Material Issue Procedure

Step 1	Material Request
Shafeer or Raees raises a written Material Issue Slip stating: Project Code, Item Name, Qty Required, Purpose. Slip is signed by the Dept Head.	
Step 2	PM Approval
Afsal reviews the request against the project BOQ and approves. No issue without Afsal's signature on the slip.	
Step 3	Issuance

Vibin issues exact quantity as approved. Excess material requests are escalated to the Director.

Step 4

Stock Update

Vibin immediately updates the Stock Register — Issued qty, date, project code, slip reference number.

Step 5

Leftover Return

Any unused material returned from site or production is received by Vibin with a Material Return Note and added back to stock.

■ NOTE: Monthly physical stock audit is mandatory. Vibin prepares the audit report and submits to Afsal and Director by the 1st of every month.

Sign-Off

Role	Name	Signature	Date
Store In-Charge	Vibin		
Admin & Project Coord.	Afsal		
Director	Yaseen		

ATI-FSOP-2025 | SOP-03 — PRODUCTION: MODULAR FURNITURE

Purpose

To establish a standardized, traceable production process for all modular furniture items including modular kitchens, wardrobes, TV units, work areas, and storage systems.

Department Head

Raees — responsible for all modular production quality, machine planning, team allocation, and delivery timelines.

Production Card

Every unit produced must have a Production Card attached. This card travels with the unit from cutting to dispatch.

Field	Details
Project Code	Assigned by Afsal at project kickoff
Client Name	As per project file
Item Description	e.g., Kitchen — Upper Cabinet Unit 1 of 6
Drawing Reference	Drawing number from Design Team
Materials Required	Board, laminate, hardware — item-wise
Assigned Carpenter	Named carpenter responsible
Target Completion	Date by which unit must be ready for QC2
QC Status	QC2 Passed / Failed — signed by Raees

Production Stages — Modular Furniture

Stage 1	Design & Drawing Review Raees reviews approved drawings with the carpenter team. All dimensions, edge details, drilling patterns, and hardware specifications are confirmed before cutting begins. Unclear drawings are escalated to Design Team via Afsal — production does NOT start on unclear drawings.
Stage 2	Material Collection from Store Raees raises a Material Issue Slip for the exact quantity needed. Vibin issues materials after Afsal's approval. Raees verifies received materials against the Production Card before beginning.
Stage 3	Panel Cutting Panels are cut using the panel saw/CNC machine as per cutting list. Cutter verifies dimensions after each cut. Cut sheets are labelled with Production Card code and stacked by project.
Stage 4	Edge Banding Edge banding applied to all exposed edges using edge banding machine. Raees spot-checks edge bond quality — no gaps, no lifting, colour match confirmed. Faulty edge bands are redone before proceeding.

Stage 5	Drilling & Hardware Fitting Preparation
Dowel holes, hinge holes, and shelf pin holes drilled as per drawing. CNC boring used for precision. Raees verifies drilling accuracy against hardware specifications.	
Stage 6	Assembly
Cabinets assembled with dowels, screws, and connectors. Squareness checked with diagonal measurement. Hardware (hinges, channels, soft-close) fitted and tested. Named carpenter signs the Production Card after assembly.	
Stage 7	Finishing — Laminate / Polish / Paint
Laminate pressed and trimmed. PU paint / melamine polish applied in polishing bay. Polisher signs the Production Card. Raees inspects finish quality before releasing to QC2.	
Stage 8	QC2 — Factory Quality Check
Raees conducts QC2 inspection (see SOP-05). QC2 Pass stamp applied on Production Card. Failed items returned for rework — no failed item proceeds to packing.	
Stage 9	Packing
Passed units wrapped in bubble wrap and stretch film. Production Card attached to outside of pack. Batch handed to Vibin for dispatch preparation.	

Daily Production Board — Modular

Raees updates the Factory Production Board every morning after the 9:00 AM task allocation meeting:

Item	Project	Stage	% Complete	Target Date	Remarks
Modular Kitchen	Project Code	Assembly	80%	DD/MM/YY	—
Wardrobe 1	Project Code	Polishing	60%	DD/MM/YY	—
TV Unit	Project Code	Edge Band	40%	DD/MM/YY	—
Crockery Unit	Project Code	QC2 Done	100%	DD/MM/YY	Ready for dispatch

■ NOTE: Raees submits a daily production report to Afsal by 6:00 PM every working day.

Sign-Off

Role	Name	Signature	Date
Head of Modular Furniture	Raees		
Admin & Project Coord.	Afsal		

ATI-FSOP-2025 | SOP-04 — PRODUCTION: CUSTOM WOODEN FURNITURE

Purpose

To define the production process for all custom-made wooden furniture items including beds, dining tables, console units, wooden paneling, wooden grills, staircase elements, and bespoke solid wood pieces.

Department Head

Shafeer — responsible for all custom wood production quality, skilled carpentry supervision, joinery standards, and finishing quality.

Production Card — Custom Wood

Same Production Card format as Modular (see SOP-03) with the addition of:

- Joinery Method: Mortise & Tenon / Dovetail / Biscuit / Dowel / Pocket Screw
- Wood Species: Mahogany / Teak / Rubber wood / MDF Core
- Polishing Specification: Natural / Tinted / PU Gloss / Matte / Charcoal

Production Stages — Custom Wooden Furniture

Stage 1	Drawing & Sample Review
Shafeer reviews approved drawings with the carpenter team. For new joinery or unique profiles, a sample piece is made and approved by the client (via Design Team) before full production begins. Sample approval is documented in writing.	
Stage 2	Timber Selection & Material Collection
Shafeer personally selects timber/boards for each job — checking grain direction, moisture content, and absence of knots or defects for visible surfaces. Materials collected from Vibin against approved Material Issue Slip.	
Stage 3	Rough Cutting & Seasoning Check
Timber rough cut to oversize dimensions. Moisture content re-verified (max 10% for solid wood furniture). Boards allowed to acclimatize in the factory for minimum 24 hours before fine cutting.	
Stage 4	Fine Cutting & Shaping
Table saw, band saw, and router used for precision cutting and profile shaping. Each piece labelled with production card code. Shafeer spot-checks 100% of cut pieces for dimension accuracy.	
Stage 5	Joinery & Assembly
Joints made as per drawing specification. Glue-up done in stages with clamps. Squareness checked at every glue-up stage. Shafeer inspects joint quality before and after assembly. Any weak joint is redone before proceeding.	
Stage 6	Sanding
Machine sanding: 80 grit → 120 grit → 180 grit. Hand sanding: 220 grit for final pass. No polish applied on unsanded surfaces. Shafeer approves surface before polishing begins.	

Stage 7	Polishing & Finishing
Wood filler applied to grain/pores. Sealer coat applied and sanded back. Colour stain applied if specified. Final PU / Melamine / Charcoal / Natural finish applied in polishing bay. Minimum 2 coats with intermediate sanding. Polisher signs Production Card.	
Stage 8	Hardware Fitting
Hinges, handles, drawer channels, soft-close units fitted. All hardware tested for smooth operation. Shafeer approves before releasing to QC2.	
Stage 9	QC2 — Factory Quality Check
Shafeer conducts QC2 inspection (see SOP-05). QC2 Pass stamp on Production Card. Rejected items returned for rework — no failed piece proceeds to packing.	
Stage 10	Packing
Custom furniture wrapped in foam padding and stretch film. Fragile/glass elements packed with additional protection and clearly labelled FRAGILE. Production Card attached to pack.	

■ *NOTE: Shafeer submits a daily production report to Afsal by 6:00 PM every working day. Includes: units in progress, stages completed, any material shortage, and projected completion dates.*

Sign-Off

Role	Name	Signature	Date
Head of Wood Working	Shafeer		
Admin & Project Coord.	Afsal		

ATI-FSOP-2025 | SOP-05 — QUALITY CONTROL (QC1 / QC2 / QC3)

Purpose

To ensure that every material, every unit produced, and every site installation meets Appletree Interiors' quality standards before proceeding to the next stage.

QC Structure

QC Level	When	What is Checked	Responsible	Approver
QC1 — Raw Material	On material receipt	Thickness, brand, moisture, colour, quantity	Vibin + Dept Head	Afsal
QC2 — Factory QC	Before packing	Dimensions, edge band, hardware, alignment, polish, finish	Raees / Shafeer	Afsal
QC3 — Site QC	After installation, before handover	Level, gaps, hardware function, finish, cleanliness, punch list	Hashim / Noushad	Afsal

■ **NOTE:** No project is closed without a signed QC3 form submitted to Afsal and Director.

QC2 — Factory Quality Checklist (Modular & Custom)

No.	Check Point	Done	Remarks
1	All dimensions match approved drawings ($\pm 1\text{mm}$ tolerance)	☐	
2	Panel surfaces free of scratches, dents, and delamination	☐	
3	Edge banding fully bonded — no gaps or lifting anywhere	☐	
4	All drill holes as per drawing — size, position, depth	☐	
5	Cabinet squareness checked — diagonals within 2mm	☐	
6	All hardware fitted and tested — hinges, channels, handles	☐	
7	Soft-close function operational on all drawers and doors	☐	
8	Laminate/veneer — colour match, grain direction as specified	☐	
9	Polish/PU finish — even sheen, no drips, runs, or streaks	☐	
10	Charcoal / fluted finish — uniform profile and colour	☐	
11	Glass panels fitted, edges polished, no chips or cracks	☐	
12	Production Card signed by carpenter and department head	☐	
13	QC2 Pass stamp applied on Production Card	☐	

QC3 — Site Installation Quality Checklist

No.	Check Point	Done	Remarks
1	All units installed as per layout drawing	☐	

No.	Check Point	Done	Remarks
2	Cabinets/wardrobes level — checked with spirit level (horizontal and vertical)	☐	
3	Gaps between units within 2mm tolerance	☐	
4	Wall gaps sealed or covered with matching filler/beading	☐	
5	All doors and drawers open and close smoothly	☐	
6	Soft-close operational — no slamming	☐	
7	All handles aligned uniformly	☐	
8	Skirting, cornice, and fillers correctly fitted	☐	
9	No visible damage from transit or installation	☐	
10	Polish/finish — no scratches from installation work	☐	
11	Electrical/plumbing cutouts align with services	☐	
12	Site cleaned of all installation debris	☐	
13	Client walkthrough conducted	☐	
14	Punch list items noted and closure timeline given	☐	
15	Client sign-off obtained on QC3 form	☐	

Sign-Off

Role	Name	Signature	Date
Site Supervisor (QC3)	Hashim / Noushad		
Dept. Head (QC2 MOD)	Raees		
Dept. Head (QC2 CWF)	Shafeer		
Admin & Project Coord.	Afsal		
Director	Yaseen		

ATI-FSOP-2025 | SOP-06 — PACKING & DISPATCH

Purpose

To ensure that all finished furniture is packed securely, dispatched with complete documentation, and delivered to site without damage.

Responsible Staff

- Packing: Carpenter team under Shafeer / Raees supervision
- Dispatch Coordination: Vibin (Store In-Charge)
- Documentation: Afsal (Admin & Project Coordinator)
- Loading Supervision: Vibin + Shafeer / Raees

Dispatch Process

Step 1	QC2 Clearance
Only QC2-passed items enter the packing area. QC2 Pass stamp must be visible on Production Card. Vibin cross-checks the packing list against QC2 approved units.	
Step 2	Packing Standards
Modular units: bubble wrap + stretch film + cardboard corner protectors. Custom wooden: foam padding + stretch film. Glass items: foam + additional cardboard, labelled FRAGILE. All packs labelled with: Project Code, Client Name, Item Description, Qty, Handling Instructions.	
Step 3	Material Dispatch Note (MDN)
Vibin prepares MDN before loading. MDN must contain: Date, MDN Number, Project Code, Client Name and Site Address, Item-wise list with quantities, Vehicle number and Driver name, Photo of loaded vehicle (mandatory), Dispatched by (Vibin signature), Approved by (Afsal signature).	
Step 4	Loading
Loading supervised by Vibin and respective Dept Head. Heavy items loaded first. Fragile items secured and padded. No overloading. MDN copy given to driver.	
Step 5	Site Intimation
Afsal informs the Site Supervisor (Hashim or Noushad) of dispatch details: MDN number, items dispatched, ETA. Site Supervisor arranges labour and access before vehicle arrival.	
Step 6	Delivery & Acknowledgement
Site Supervisor receives delivery, physically counts all items against MDN. Any damage or shortage noted on MDN before signing. Signed MDN photo sent to Afsal within 30 minutes of delivery.	
Step 7	Stock Update
Vibin updates Stock Register and project records after confirmed delivery. MDN filed in project folder by Afsal.	

■ *NOTE: GPS timestamp on vehicle dispatch is recommended. All MDN photos to be stored in the project folder.*

Sign-Off

Role	Name	Signature	Date
Store In-Charge	Vibin		
Admin & Project Coord.	Afsal		
Dept. Head (Dispatch)	Raees / Shafeer		

ATI-FSOP-2025 | SOP-07 — DAILY FACTORY ROUTINE

Purpose

To establish a disciplined, structured daily routine across the factory ensuring maximum productivity, safety, cleanliness, and accountability every working day.

Daily Schedule

Time	Activity	Responsible	Action Required
8:30 AM	Attendance	Shafeer / Raees	All staff mark attendance. Absentees reported to Afsal immediately.
8:45 AM	Factory Inspection	Dept Heads	Walk the floor — check cleanliness, machine condition, yesterday's pending work.
9:00 AM	Daily Production Meeting	Afsal + Dept Heads	Review production board. Allocate tasks per carpenter. Resolve material or drawing issues.
9:15 AM	Task Allocation	Shafeer / Raees	Each carpenter briefed on today's task, drawing, and target output.
9:30 AM	Production Begins	All Production Staff	Work as per task allocation.
1:00 PM	Lunch Break	All Staff	30 minutes.
1:30 PM	Production Resumes	All Production Staff	Continue tasks.
5:00 PM	Progress Check	Shafeer / Raees	Walk the floor — check progress vs morning targets. Escalate delays to Afsal.
5:30 PM	Machine Cleaning & Shutdown	Mohanan + Team	All machines cleaned and switched off. Sawdust and offcuts cleared.
5:45 PM	Daily Production Report	Shafeer + Raees	Submit output report to Afsal (units completed, in-progress, issues).
6:00 PM	Factory Secured	Last Dept Head out	All doors locked, lights off, security check completed.

Weekly Routines

Day	Activity	Responsible
Monday	Weekly production planning meeting. Review all active projects, set week targets.	Afsal + Dept Heads
Wednesday	Mid-week production review. Check against weekly targets. Flag delays.	Afsal + Dept Heads
Friday	Stock check — Vibin reviews fast-moving items and raises reorder requests.	Vibin
Saturday	Deep cleaning of factory floor, machines, and storage area.	Mohanan + All Staff
Saturday	Weekly dispatch summary sent to Director.	Afsal

Monthly Routines

Activity	Responsible	Deadline
Physical stock audit — all materials counted and reconciled	Vibin + Afsal	1st of every month
Machine maintenance and servicing schedule review	Mohanan + Dept Head	1st of every month
Production efficiency report — output vs target	Afsal	5th of every month
Profitability review per project	Basith + Afsal	5th of every month
Staff performance review — output, quality, attendance	Director + Afsal	Last week of month

Safety & Housekeeping Rules

- All machine operators must wear safety glasses and ear protection when using machinery.
- No loose clothing near rotating machines. No mobile phone usage on the production floor during operating hours.
- Fire extinguisher location: near the main entrance and polishing bay. Monthly check by Mohanan.
- First aid kit: Admin area. Responsible: Afsal.
- Sawdust and wood offcuts must not accumulate — cleared every 2 hours by the carpenter on duty.
- Polishing area is a no-smoking zone at all times.
- Spills (paint, glue, polish) cleaned immediately by the person responsible.

Sign-Off

Role	Name	Signature	Date
Head of Wood Working	Shafeer		
Head of Modular	Raees		
Admin & Project Coord.	Afsal		
Director	Yaseen		

ATI-FSOP-2025 | SECTION 10 — FORMS & CHECKLISTS INDEX

The following forms are mandatory operational documents. Each form must be completed, signed, and filed in the project folder. Digital copies must be maintained in the company's ERP/admin system.

Form Code	Form Name	Used In	Raised By	Approved By
ATI-F01	Material Request (MR)	SOP-01 / SOP-02	Shafeer / Raees	Afsal
ATI-F02	Purchase Request (PR)	SOP-01	Vibin	Director
ATI-F03	Purchase Order (PO)	SOP-01	Vibin	Director
ATI-F04	Goods Receipt Note (GRN)	SOP-01	Vibin	Afsal
ATI-F05	Material Issue Slip	SOP-02	Dept Head	Afsal
ATI-F06	Material Return Note	SOP-02	Vibin	Afsal
ATI-F07	Production Card	SOP-03 / SOP-04	Afsal	Dept Head
ATI-F08	QC1 Raw Material Checklist	SOP-05	Vibin	Dept Head
ATI-F09	QC2 Factory Checklist	SOP-05	Raees / Shafeer	Afsal
ATI-F10	QC3 Site Checklist	SOP-05	Hashim / Noushad	Afsal
ATI-F11	Material Dispatch Note (MDN)	SOP-06	Vibin	Afsal
ATI-F12	Daily Production Report	SOP-07	Raees / Shafeer	Afsal
ATI-F13	Monthly Stock Audit Report	SOP-02	Vibin	Director
ATI-F14	Client QC3 Sign-Off Form	SOP-05	Hashim / Noushad	Director

This SOP document is the property of Appletree Interiors. It is confidential and intended for internal use only. All staff are required to comply with these procedures. Non-compliance must be reported to the Director. This document will be reviewed annually or upon any significant process change. Version 1.0 — Effective: 18 June 2026

APPROVED BY — DIRECTOR, APPLETREE INTERIORS

Sign-Off

Role	Name	Signature	Date
Director	Yaseen		
Date			
Signature			